

## Car Park Decking-DCU



McKeon Construction Ltd approached Larsen Contracts seeking a durable and innovative resin waterproofing system to refurbish a multi-storey car park where the existing deck coating had started to fail.

Extremely quick installation is feasible with the main system of 2-3mm being installed in a single application process.

Despite bad weather conditions during the February installation, the unique two-hour cure time of the CP TD system (which is unaffected by temperature) allowed Larsen to install the new decking within two days and with much less disruption than a standard resin based decking system.

### Project Details:

**Client:** Dublin City University

**Main Contractor:** McKeon Construction

**Specialist Contractor:**  
Larsen Contracts Ltd

**Application:**  
Degafloor CP TD system –flexible,  
seamless , slip resistant finish

**Market:**  
Education, Car Park Decking & Markings