

Resin flooring
Commercial screeding
Concrete Repair
External renders
Resin Injection
Structural waterproofing
Car park & Podium decking
Reservoir refurbishment
Chemical resistant Bund Lining

Fast Track Systems

Belfast 0044 (0)28 90774000

Manchester 0044 (0)161 2193624 London 0044 (0)203 3285100 Dublin 00353 (01) 8348255

info@larsencontracts.co.uk

Supervalu HollyHill, Cork

Resin Flooring

Larsen Contracts recently undertook replacement of Resin flooring at the **Supervalu Supermarket** in Cork. Supervalu, a major national supermarket Chain and part of the Musgrave group appointed Larsen Contracts as main contractor to install 1100m2 of a new quick drying Resin flooring system by Degafloor. This was an initial trial with potential for roll out to stores nationwide

The application specified for the main store areas was Degafloor MMA resin with decorative flake finish .This is a fast drying seamless epoxy resin system that cures within 2 hours offering the client minimal down time . This system offers excellent durability with a unique chemical bonding between layers; it comes with a ten year warranty when the maintenance regime is adhered to.

Project Details:

Client: Musgrave Retail Partners, Cork

Main Contractor: Larsen Contracts

Application: Degafloor MMA

Decorative flake finish & Degafloor FB

anti -slip for Deli counters

Supplier: Degafloor

Sector: Retail Industry

The high gloss, joint-free finish of this floor coating eliminates the cracks and crevices that can harbour dirt and food spills - making the floors hygienic as well as being easy to clean. The Decorative Flake finish chosen was attractive and bright for a consumer environment. At Deli Counters Degafloor FB anti-slips system was used Where there was higher risk of slippage





Larsen Contracts completed 1100m2 of flooring in sections over 5 visits from 8pm to a 7am handover each morning, offering minimal disruption to the client and customers. At each session 300m2 was completed within a "Live Shop" including all preparatory works which included securing of food stuffs with protective covering, removal of aisle items as required, and necessary repairs to existing sub flooring.