Larsencontracts

Resin flooring
Commercial screeding
Concrete Repair
External renders
Resin Injection
Structural waterproofing
Car park & Podium decking
Reservoir refurbishment
Chemical resistant Bund Lining
Fast Track Systems

Belfast 0044 (0)28 90774000

Manchester 0044 (0)161 2193624
London 0044 (0)203 3285100
Dublin 00353 (01) 8348255

info@larsencontracts.co.uk
www.larsencontracts.co.uk

Bund Lining

Takeda (Ireland ltd)

Takeda is a Japanese global pharmaceutical company. Larsen were recently contracted to replace Bund linings at the Grangecastle manufacturing facility in Dublin .This is Takeda's worldwide Centre for Active Pharmaceutical Ingredient (API) manufacturing, development and technical support .

The remedial works to Takeda's large Bund store and tank farm and covings were carried out during a two week shutdown; a temporary weatherproof structure was erected over the entire tank farm to ensure weather did not disrupt the programme. *Early Morning and Late shifts were worked by the Larsen team to meet the demanding programme and deadline*

Health and Safety was paramount in an EX rated area as the project included lining works to over 300sqm including Hydrochloric and Caustic Bunds.

Larsen undertook preparation, by high pressure water blasting of the existing Bund walls, floors and plinths. Concrete repair and crack injection works to tank farm included breaking out defective boast concrete and making good with application of Remmers Betofix and Remmers Epoxy Injection resin. The chemical resistant lining was the Remmers SD1 Silicate mortar system.

The Bund Store joints were also repaired with works including: setting up a spill containment sock, removal of existing join sealant, cleaning and priming, and application of a polyurethane joint sealant.

Project Details:

Client:
Takeda (Ireland)

Consulting Engineers: McElroy Associates

Specialist Contractor:
Larsen Contracts Ltd

Application: Remmers FAS 100 / Injection resin EP, Remmers SD1 Silicate Mortar

Market: Pharmaceutical