

Resin flooring Commercial screeding Concrete Repair External renders Resin Injection Structural waterproofing Car park & Podium decking Reservoir refurbishment Chemical resistant Bund Lining Fast Track Systems

Belfast 0044 (0)28 90774000

Manchester 0044 (0)161 2193624 London 0044 (0)203 3285100 Dublin 00353 (01) 8348255

> info@larsencontracts.co.uk www.larsencontracts.co.uk

Tower Reservoir Refurbishment - Arklow

Larsen Contracts has successfully completed the rehabilitation of the main water tower reservoir (as pictured below) located in the town of Arklow, Co. Wicklow. The project included both internal and external refurbishment of the tower reservoir as well as the internal refurbishment of the secondary underground reservoir in accordance with The Confined Space Regulations.



Project Details:

Location: Lamberton, Arklow, Co. Wicklow

Client: Irish Water

Main Contractor: MJS Engineering

Specialist Contractor: Larsen Contracts Ltd

Application:

Repair defective concrete; resin injection; protective and waterproof coatings applied to entire structure (internally & externally).

Market: Civil, Utilities

The aim of the refurbishment works was to tend to general structural damage (including joint repair, cracks and visible leaks) and to extend the life of the reservoirs – in order to achieve this, special care was taken in identifying defective areas of the structure; which were then mechanically removed, treated and repaired. Once the construction joints were restored and resin was injected, the application of a cementitious fairing coat was applied to all surfaces of the tank, followed by two layers of a DWI approved waterproof coating, which was applied internally. Finally, two layers of anti-carbonation paint were applied to the external surfaces.



Resin flooring Commercial screeding Concrete Repair External renders Resin Injection Structural waterproofing Car park & Podium decking Reservoir refurbishment Chemical resistant Bund Lining Fast Track Systems

Belfast 0044 (0)28 90774000

Manchester 0044 (0)161 2193624 London 0044 (0)203 3285100 Dublin 00353 (01) 8348255

> info@larsencontracts.co.uk www.larsencontracts.co.uk

Works on the reservoirs involved:

- Survey and investigative works to the existing structure;
- Structure testing;
- Cut out and reinstate defective areas including treatment of reinforcement;
- Joint sealing to all construction and expansion joints;
- Power washing to surfaces;
- Resin injection to specific areas;
- Application of fairing coat to surfaces;
- Application of DWI approved waterproof coating to internal surfaces;
- Anti-carbonation paint applied externally.

*All internal works were carried out in accordance with The Confined Spaces Regulations. *All internal material used was DWI approved.

